

CITY OF LA VISTA
MAJOR AND CITY COUNCIL REPORT
MARCH 20, 2012 AGENDA

Subject:	Type:	Submitted By:
AWARD CONTRACT BACK STOP REPLACEMENT	◆ RESOLUTION ORDINANCE RECEIVE/FILE	JOE SOUCIE PUBLIC WORKS DIRECTOR

SYNOPSIS

A resolution has been prepared to approve a contract with Elkhorn Fence Company, Elkhorn, Nebraska for replacement of the backstop on field #3 at the Sports Complex in an amount not exceed \$5,296.00.

FISCAL IMPACT

The FY 2011/12 General Fund Budget provides funding for the proposed project.

RECOMMENDATION

Approval

BACKGROUND

The backstop on field #3 at the Sports Complex is structurally deficient and poses a safety risk. Park Superintendent Brian Lukasiewicz solicited bids and recommends Elkhorn Fence Company as the low compliant bidder.

Elkhorn Fence Company	\$5,296.00
American Fence Company	\$5,825.77
Monarch Fence Company	\$6,837.00

RESOLUTION NO. _____

**A RESOLUTION OF THE MAYOR AND CITY COUNCIL OF THE CITY OF LA VISTA,
NEBRASKA, AWARDING A CONTRACT TO ELKHORN FENCE COMPANY, ELKHORN,
NEBRASKA IN AN AMOUNT NOT TO EXCEED \$5,296.00**

**WHEREAS, the City Council of the City of La Vista has determined that the replacement of
the backstop on field #3 at the Sports complex is necessary; and**

WHEREAS, the FY 2011/12 General Fund Budget will provide funds for this project; and

**WHEREAS Subsection (C) (9) of Section 31.23 of the La Vista Municipal Code requires that
the City Administrator secures Council approval prior to authorizing any purchase
over \$5,000.00.**

**NOW, THEREFORE, BE IT RESOLVED, that the Mayor and City Council of La Vista, Nebraska
award the contract to Elkhorn Fence Company, Elkhorn, Nebraska in an amount
not to exceed \$5,296.00**

PASSED AND APPROVED THIS 20TH DAY OF MARCH, 2012.

CITY OF LA VISTA

Douglas Kindig, Mayor

ATTEST:

**Pamela A. Buethe, CMC
City Clerk**



ELKHORN FENCE CO.

P.O. Box 186

Elkhorn, NE 68022

Office 402-289-4945 / Fax 402-289-5566

To:
LaVista Parks

Attn:
Brian Lukasiewicz

Date: 3/8/12

Phone: 402-331-8927

Fax: 402-331-1051

Project Name:
Replace Backstop

Project Location:
LaVista Sports Complex

Elkhorn Fence proposes to supply all materials and labor to remove existing and install new 20'tall, hooded, galvanized chain link backstop for:

\$ 4,940.00 + \$ 147.00 tax on materials if applicable

Specifications:

- Materials to match backstop to the northeast with layout/footprint to match existing.
- 4" OD SS40 posts set in 16" x 4' concrete footings. (Posts set 1' taller to accommodate field elevation)
- 1-5/8" OD SS40 horizontal rails.
- 2"x9ga. standard 1.2 OZ. galv. chain link mesh throughout. (6ga fabric across the back above 3 – 2x12 planks.)
- **For (2) 3' wide x 6' tall single swing gates hung between the backstop and sideline fences ADD \$356.00 + \$20.00 tax on materials if applicable.**

Fence to conform to drawings and written specifications and installed in a professional manner.

Price includes Mobilizations to site.

Price assumes the entire fence line to be accessible by large skid-steer loader and the ability to dig post holes with hydraulic auger.

Project to be finish graded and ready for all fence installation upon notice to proceed and mobilization to the site. This proposal to be attached to the Contract/Sub-contract as an Exhibit/Amendment to the Contract upon acceptance.

Price good for **30** days.

Submitted by:

A handwritten signature in black ink that appears to read "Rob Brooks".

Accepted By:

Rob Brooks

402-677-8677 cell

LaVista Backstop propII

4,940.00

356.00

5,296.00

AMERICAN FENCE COMPANY

14803 Frontier RD
Omaha, NE 68138
(402)896-6722
Fax(402)896-0692

1922 Delaware
Des Moines, IA 50317
(515)265-6100
Fax(515)265-6108

3301 N. 35TH Street
Lincoln, NE 68504
Phone: (402)467-2511
Fax: (402)467-2512

2205 E. Hwy. 30
Grand Island, NE 68802
(308)395-0793
Fax(308)395-3901

27083 Morton Court
Sioux Falls, SD 57108
(605)371-4577
Fax(605)371-1771

Date: 2/27/2012 Phone: 331-8927

Fax: 331-1051

Specification for Fencing

Customer Name: City of LaVista

ATTN: Brian Lukasiewicz

Overall Length

Overall Height

Billing Address: 9900 Portal Road

40'

10' tall w/ 10' canopy

Location of Job: LaVista Sports Complex

Wire Gauge

Dia. Corner/End Post

City: LaVista

State: NE

Zip: 68128

6 and 9 gauge galv.

4"

Dia. Line Post

Dia. Top Rail

4"

1-5/8"

Walk Gates

Drive gates

none

none

Notes & Exclusions:

- 1.) Unless otherwise noted, one mobilization is included for the installation of the fence.
- 2.) Unless otherwise noted, block-out(s) in concrete / masonry for fence by others. No core drilling included.
- 3.) No surveying and/or staking included. Fence line to be staked by others.
- 4.) Unless otherwise noted, no removals, grading, grubbing and/or demolition are included.
- 5.) Private utilities to be located by others. Fence line to be staked clear of utilities. Extra handwork due to interference with utilities is not included.
- 6.) Unless otherwise noted, no electrical wire, wiring, grounding, conduit and/or connections included.
- 7.) No bonds, dues, or completed operations included.
- 8.) All items not specifically mentioned in this proposal are excluded.
- 9.) Unless otherwise noted, no addenda were received.
- 10.) This proposal may be withdrawn by AFC if not accepted within thirty days.
- 11.) AFC will not be subject to liquidated damages.
- 12.) Entire fence line must be concrete truck accessible.
- 13.) Waivers of subrogation are not included.
- 14.) AFC will need 30 working days to complete the project.

Diagram

Remove existing backstop at field # 3.

Furnish and install 1 each 40' backstop including wings and canopy; 20' straight stretch at backstop shall have 6 gauge galvanized fabric at 7' tall. Includes 3 rails. Backstop 20' stretch shall include 4 each angle brackets for owner provided backstop boards.

Canopy and wings shall include 9 gauge galvanized fabric and 3 each rails. Rails at wings shall be set at 2"; 5' and 9'-10"; rails 30' backstop stretch shall be set at 3'; 6'-6" and 9'-10"; canopy shall have one top and middle rail.

Please allow 2 to 3 weeks lead time for 6 gauge fabric.

No netting, netting removal, gates, grading, backstop boards, or paint included.

For tax please add \$259.13 if applies.

Owner shall furnish form 17 for tax exemption or tax will be added at time of billing.

Line Item: Furnish and install 2 each 32" wide x 72" tall single swing gates with fork latch. Please add: \$590.13.

Please call Chris Kudlacz at 402-616-6856 with any questions.


NOTE: NOT RESPONSIBLE FOR SPRINKLERS SYSTEMS. ESTIMATE GOOD FOR 15 DAYS.


Customer assumes full responsibility for the location of property pins, staking of the fence, and any inaccurately placed pins and/or stakes. Customer understands that AFC has staked the fence based on the proposal and/or in consideration of existing utilities that may not reflect the actual location of customer's property. Customer agrees to defend, hold harmless and indemnify American Fence Co. from and against all claims, liabilities and expenses for trespass and other damage or loss arising out of the location of said fence. Customer hereby assumes full responsibility for the damage to any marked and unmarked underground utility, telephone, T.V., cable or sprinkler system pipes. If the customer requests, agrees or allows American Fence Company to locate the fence within 18 inches of any buried utilities, the customer agrees to defend, hold harmless and indemnify American Fence Company from and against all claims, liabilities and expenses as a result of damage to these utilities and related property. If the contract price is not paid when due, the customer agrees to allow American Fence Co. to trespass on to their property and remove the fence at the company's discretion. Furthermore, the shall be in writing and shall be affixed to the original bid. This agreement and any subsequent modification/s shall be contingent upon strikes, accidents, shortages or delays beyond the control of American Fence Co. Any time stated for installation is purely estimated. The customer agrees and accepts that to the fence due to varying ground conditions are not the responsibility of American Fence Co. Customer to carry fire, tornado and other necessary insurance. This proposal cannot be withdrawn by customer after acceptance of proposal. American Fence Co. has the right to reject any bid. All legal and related fees accrued in an effort to collect on this account for whatever reason will be the responsibility of the customer. By signing this proposal, the customer has completely reviewed and agreed with the prices, specifications and conditions as stated herein. Furthermore, the customer is authorizing American Fence Co. to complete the work. The customer is financially responsible for cancellation fees and costs of special order materials. In the event the customer elects to cancel the contract. TERMS: 60% Down. Balance due on date of completion. A service and handling charge of 5% per month-60% per annum will apply to delinquent accounts past 10 days.

Due to unprecedeted steel price increases, contractor to pay for stored materials or provide for subsequent future price increases after award of contract. AFC will provide storage.

Accounts not paid within thirty days will be charged eighteen percent (18%) per annum.

We agree to provide the work in accordance with the information stated here in the amount of:

Authorized Signature: 

Customer/Contractor Signature: 

5825.77

\$5,825.77 No tax included.

Date: 2/27/2012

Date:

MONARCH FENCE INC.

Custom Built Fences

Patio Fences

Dog Kennels

741 W 6th St

Papillion, NE 68046

(402) 339-9340 Fax (402) 592-4406

Gate Manufacturing

Tennis Courts

Backstops

402-651-2789 (C)

Customer's Name Brian Lukasiewicz / City of La Vista

Address La Vista Sports Complex (S. of 66th & Harrison) City La Vista

Email Address blukasiewicz@ci.la-vista.org

FENCING PROPOSAL


Date 3-1-12

State NE Zip

Phone 402-331-8927 (W)

402-331-1051-Fax

Specifications	
Galvanized Vinyl Coated (BLK, BR, GR) Chain Link Fence	
Overall Length	Overall Height
40'	10' w/ "Cover"
Walk Gate(s)	Drive Gate(s)
(2) 30"	
Wire Gauge	Dia. Corner Post
4g & 6g	4"
Dia. Line Post	Dia. Top Rail
—	1 1/8"
Wood Fence	
Overall Length	Overall Height
Style	
Gate(s)	Post(s)
PVC Fence	
Overall Length	Overall Height
Style	
Color	Post(s)
Gate(s)	
Ornamental Iron/Aluminum Fence	
Overall Length	Overall Height
Style	
Color	Post(s)
Gate(s)	



NOTES:

Replace current backstop with
same as field #1

460.28

(2) gates

1420.28

(2) end supports on wood backstop

1395.45

Primer & Paint to change structure

600.00

Painted

Painted on wood

Painted on wood

\$6,837.00

Customer's Signature Brian Lukasiewicz

Date 3-1-12

Method of Payment On Completion

Date 3-1-12

Agree to terms/thru

Personalized Service...Expert Workmanship...Guaranteed!